EGGLESTON & KRENZER ARCHITECTS, PC

The Trolley Bldg 1391 East Genesee Street Skaneateles, New York 13152

October 1, 2021

Town of Skaneateles Planning Board 24 Jordan Street, Skaneateles, NY 13152

Re: Nathan Card, Card Mowing LLC - Major Special Permit Amendment 4440 Jordan Road - Tax Map # 023.-02-24.0

## NARRATIVE

The property at 4440 Jordan Road is 471,21 SF, has 278.2 ft of road frontage on Jordan Road in the IRO District. The property was developed for the Card Mowing, a Service Business in 2014 with the construction of a 5,227 SF heated building, 3,200 SF unheated storage building and a 40 ft x 80 ft concrete slab with bins for landscape material storage. The site has a tarvia driveway and gravel parking area, septic system and large stormwater bio swale area adjacent to Jordan Road. The site is served by Town water. The ISC is 15.1% and the TSC 15.3%.

This application is to expand the gravel parking area 120 feet and construct a 40 ft x 80 ft unheated storage building adjacent to the existing storage building and a 40 ft x 80 ft heated storage building adjacent to the concrete slab for outdoor storage. Two additional 30 ft x 30 ft concrete slabs will be places at the end of each building for additional outdoor storage. The ISC will be 22.1% and TSC will be 22.7%.

The bio-swale installed at the west end of the property is oversized and able to take the additional stormwater for this expansion. The buildings will have stone drainage strips under the eaves. Two LED flood lights on motion detectors, dark-sky compliant, will be located on each building. The operation of the site will remain the same in that employees report to the site, park and then take company vehicles to their work sites. Company vehicles and equipment are stored inside with landscape materials such as mulch, stone and top soil are stored outside in bins. The area disturbed will be less than one acre. Silt fence will be used for erosion control during construction.

## CONSTRUCTION SEQUENCE

- 1) Install silt fence, maintain during construction.
- 2) Remove brush ant trees for expanded area and level off the area.
- 3) Place stone base for parking, driveway and building areas.
- 4) Drill holes for post frame structures. Erect pole barns.
- 5) After siding, and trim are complete, box in drainage strips under the eaves.
- 6) Pour concrete pads for outdoor storage areas.
- 7) Box in final parking area, finish grading, spread topsoil, seed, plant landscape and mulch. Water during dry periods.
- 8) After lawn is established, remove silt fence, patch disturbed areas.

(315) 685-8144



