EGGLESTON & KRENZER ARCHITECTS, PC

The Trolley Bldg 1391 East Genesee Street Skaneateles, New York 13152

February 7, 2025

Town of Skaneateles Planning Board 24 Jordan Street Skaneateles, NY 13152

Re: Richard and Marie Garlock – Site Plan Review, Special Permit 1777 Russells Landing Tax ID# 063.-03-05.0

NARRATIVE

The property at 1777 Russells Landing is 17,590 SF, 75 FT wide with 80.4 Lin FT of shoreline. It has a 3 bedroom dwelling built in the 1960's, garage with loft, small shed and has 14.6% of the lot area as potential living space and as 9.4% building footprint. A Special Permit and Variance were granted last year for redeveloping the house and converting the garage into guest space. A new four bedroom septic system has been designed and approved for the property. The ISC was reduced to 12.6% and TSC to 22.2%. There are 453 SF of shoreline structures and 288 SF of off-shore structures. The property is in the RF zoning district and Skaneateles Lake Watershed.

This application is to redevelop the lakefront by modifying the on-shore deck, stairs and shed. These will remain 453 SF. The north side yard setback of the deck will be increased from 10.2 ft to 14.2 ft. The existing dock will be enlarged with a steel pile structure to be 8 ft wide maximum width and extend 67.5 feet into the lake. A 299 SF boat canopy with 6 ft wide docks surrounding an 11 ft x 23 ft boat slip will make for a total of 995 SF off-shore permanent structures. The height of the boat canopy will be 15 feet above high water. The dock will be a maximum 10 ft above the lake bed. The perimeter envelope will be 3,560 SF.

In addition, some modifications will be made to the approved decks and walkways between the house and guest space making for a more efficient circulation and use of the space. The ISC will remain at the approved 12.6% ISC and the TSC will be reduced to 22.1%

Silt fences will be placed below the work area to mitigate any potential erosion during construction. A floating silt curtain will be placed in the lake while the steel piles are driven and construction occurs over the water. Most of the lakefront work will be done from a barge. The original approved plan as modified will be completed including the stormwater management.

CONSTRUCTION SEQUENCE

House and Guest Space

- 1) Mark septic leach field to prevent construction traffic or staging over this area.
- 2) Install silt fence, maintain during construction.
- 3) Install storm drains to lake. Patch trench in side hill, cover with mulch and jute mesh.
- 4) Excavate for new foundation under entry addition, construct new foundation walls and deck footings .
- 5) Back fill around foundation, spread straw for erosion control.
- 6) Construct addition and roof modifications.
- 7) After roof, walls and siding are complete, install roof gutters and tie down spouts into drainage system towards lake.
- 8) Replace retaining walls.
- 9) Finish grading, install permeable walks, patio, remove old driveway, box out new driveway, spread top soil, seed or landscape and mulch. Water during dry periods.
- 10) After lawn is established, remove silt fence, patch disturbed areas of lawn.

Lakefront

- 1) Install floating silt curtain, maintain during construction.
- 2) Remove docks and decking that will not remain.
- 3) Install steel piles and dock framing.
- 4) Construct composite decking on dock and Boat Canopy structure.
- 5) Rebuild on-shore decks, shed, retaining wall and stairs.
- 6) Patch disturbed areas with native ground cover.
- 7) After water is cleared, remove floating silt curtain.





