memorandum

To:

Karen Barkdull,

EDR Project No:

15092

Planning Board Clerk

Town of Skaneateles

From:

Jo Anne C. Gagliano, RLA, President

Date:

May 2, 2018

Reference:

Neumann Residence lake front stair and seawall replacement

2923 East Lake Road Skaneateles, NY 13152

Minor Special Permit - Site Plan Review

Project Description:

The project site is located on a 0.65-acre residential property in the Rural and Farming District (RF) along the Skaneateles Lake waterfront, within the lake watershed overlay district (LWOD). The property is an existing non-conforming lot, based on overall lot size, side yard and lake-yard setbacks, and lot coverage. The Property Owner received a Variance/Special Permit from the town in 2008. Existing use is residential, an allowed use, as are adjacent properties to the north and south. Neighboring properties to the east, across East Lake Road, are wooded, undeveloped land, and residential use.

The existing property includes a single-family residence with one accessory structure, a gazebo, a stone barbeque grill, lakefront stairs, and a seawall. A paved driveway provides vehicle access from East Lake Road to the residence. Vegetation consists mainly of maintained lawn areas, with wooded vegetation at the northeast corner and along the road, and mature trees located sporadically around the property. The waterfront slope is vegetated with a continuous planting bed. Fencing runs along the top of the seawall. There is a gate at the top of the lakefront stairs.

Proposed improvements include removal and replacement of the lakefront stairs and a portion of the seawall on either side of the stairs. Stair and seawall construction are integral in both the existing and proposed reconstruction condition. The new seawall and stair layout will match the existing alignment, with a minor decrease in coverage area, due to the reduced stair width and elimination of the existing stair cheek walls. Total area of existing shoreline structures (seawall and lakefront stairs) is 347 square feet. Coverage area of existing and proposed shoreline structures complies with zoning code §148-36 A (1) (c) [2]. The existing and proposed height of the stairs above the take line (mean high water elevation) is 7 feet 6 inches. Height of the stair structure above take level complies with zoning code §148-36A (1) (d).

The total existing impervious surface coverage is 21.1 %, including all existing structures and site features. Proposed improvements will result in a minor reduction of total impervious surface coverage to 21.0% Proposed construction will not increase encroachment into setbacks. Drainage patterns will remain generally the same. The character of the property will remain consistent with neighboring residential properties. Proposed property use remains unchanged; therefore, the proposed action will not have an adverse effect on surrounding land uses.

Proposed work will be performed above and below the mean high water (MHW) elevation of 865.02. The total planned seawall and stairs disturbance area is approximately 310 square feet, or 0.007 acres. Total length of seawall and stair reconstruction along the lake line is 24 feet, including approximately 18 linear feet of seawall and 6 feet (width) of the

Landscape Architecture - Civil Engineering - Regulatory Compliance - Ecological Resource Management

Cultural Resource Management - Visual Impact Assessment - Community Planning - Golf Course Architecture

new stairs Disturbance area above MHW is approximately 215 square feet. Disturbance area below MHW is approximately 85 square feet.


The proposed seawall and stair replacement work is subject to NYSDEC and ACOE regional permits. A NYSDEC Joint Application Form for NYSDEC 401 Water Quality Certification/Article 15, and ACOE Section 404 Clean Water Act, Nationwide Permit No. 3 (Maintenance) was submitted on May 3, 2018. Since the project is part of an action being reviewed under the State Environmental Quality Review (SEQR) by the local municipality (Town of Skaneateles), completion of the SEQR process, and documentation to that effect, will be required before NYSDEC will issue the Article 15 permit.


Temporary erosion control measures will be implemented to stabilize disturbed areas and to protect the shoreline and lake during stair construction. Temporary dewatering systems and water quality protection measures must comply with NYSDEC/ACOE permit and City of Syracuse Water Department requirements. No trees will be removed by the proposed work. Existing vegetative cover will be re-established on the shoreline slope following construction.


Copies To:

file

Chris and Amy Neumann







RETURNIN RESIDENCE LACEFRONT STARR REPLACEMENT

WE A BECOME TO A STARRED TO STARR REPLACEMENT

REAL DISCUSSION & SEQUENTI OF DEFAULTS

RECORDOR & SEQUENTI OF DEFAULT

NEGRICAN RESIDENCE: LAVE STATEMENT ASSETS AND THE STATEMENT OF STATEME

C-602

FOR MUNICIPAL REVIEW ONLY NOT FOR CONSTRUCTION