EGGLESTON & KRENZER ARCHITECTS, PC

The Trolley Bldg 1391 East Genesee Street Skaneateles, New York 13152

Town of Skaneateles Planning Board 24 Jordan Street, Skaneateles, NY 13152 June 6, 2024

Re: Daniel and Jennifer Seidberg- Shoreline Restoration Site Plan Review and Special Permit 2500 Lakefront Lane Tax Map # 054.-03-01.1

NARRATIVE

The Seidberg property is 17,536 SF, 91.6 ft of lake frontage and 91 ft frontage on Lakeview Lane in the RF District and Skaneateles Lake watershed. It has a single family dwelling with detached garage, porches, patio, sheds and stairs down to a 181 SF deck/dock at the shoreline. The ISC is 15.9% and TSC to 19.6%. The on-shore structures total 354 SF and off-shore structures are 258 SF where 400 SF and 800 SF are allowed respectfully. The half of the area within 50 ft of the Lake is steep slope greater than 30% that has severe erosion and undermined issues.

This application is to construct a seawall and two additional retaining walls to stabilize the bank, rebuild the stairs to the lake adding a 11' x 14.5' deck and rebuild the dock with a 100 SF platform at the Lake. The total off-shore improvements are 742 SF and the total on-shore improvements 400 SF. The ISC will remain 15.9%. The TSC will be 19.8%. This will allow for winter storage of the temporary dock sections and boat hoists.

The perimeter envelope is 2,005 SF. The side yard setback from the property line projected from the center line of the Lake is 15.6 ft on the north and 10 ft on the south. The level of the dock will be at 100-year flood level (867.0 ft) and no higher than 6 ft above the lake bed.

A floating silt curtain will be placed around the dock and work area during construction and will be removed after the lake water has cleared. Most of the work will be done from a barge. The tiers between the retaining walls will be landscaped with native species bushes, ground cover and trees.

Site Plan Review for the shoreline structures and bank stabilization is required and a Special Permit for the change of grade within 50 ft of the lake line.

CONSTRUCTION SEQUENCE

- Install floating silt curtain and sediment logs and maintain during construction.
- 2) Remove existing dock/deck structure.
- 3) Construct tiered retaining walls utilizing the cut and fill of the existing bank
- 4) Install new steel piles and frame work for dock and platform.
- 5) Install dock, deck and platform surface decking. Construct stairs and fences.
- 6) Plant ground cover, bushes and trees surrounded by mulch.
- 7) After lake water is clear, remove floating silt curtain.

(315) 685-8144

