EGGLESTON & KRENZER ARCHITECTS, PC

The Trolley Bldg 1391 East Genesee Street Skaneateles, New York 13152

March 27, 2025

Town of Skaneateles Planning Board 24 Jordan Street Skaneateles, NY 13152

Re: Bradley and Kelly Wilson -Special Permit/Site Plan Review 2949 West Lake Road

Tax Map# 051.-02-10.0

NARRATIVE

The Wilson property is 73,265 SF with 229 ft of frontage on West Lake Road. It is improved with a single family dwelling, detached garage, deck, walkways, septic system, well and driveway. The building footprint is 3,163 SF and the property is 1,600 ft from the lake. The ISC is 10.2% and TSC is 10.5%. The property is in the RF zoning district and Skaneateles Lake watershed. The detached garage is in poor condition.


This application is to remove the detached garage and replace it with a 26' x 36' two car garage with a one-bedroom accessory dwelling on the second floor that is 1,000 SF. A 10' x 12' deck is off the north side of the new dwelling. An existing impermeable walkway will be replaced with a permeable walkway. A new septic system is being designed for the accessory dwelling. The resulting ISC will be 10.0% and TSC 10.8%. In that the property is less than two acres, a Special Permit is required for the accessory dwelling.

Silt fence will be placed below the work area to control any potential erosion during construction. The accessory dwelling will utilize the existing dwelling's well and electric service.

CONSTRUCTION SEQUENCE

- 1. Install silt fence or sediment logs below work area, maintain during construction. Mark proposed septic area with a fence to protect from construction traffic and storage.
- 2. Remove the existing detached garage and excavate for new foundations.
- 3. Construct new foundation and back fill. Frame new structure.
- 4. After roof and fascia are complete, install roof gutters and direct downspout away from disturbed areas.
- 5. During dry period, install new leach field system.
- 6. After siding and trim are complete, block out final driveway and walkways. Finish grading, spread topsoil, seed and mulch over any disturbed areas. Water during dry periods.
- 7. After lawn is established, remove silt fence/sediment logs.

(315) 685-8144





GARAGE/ACCESSORY
APARTMENT:
BRADLEY & KELLY WILSON
2949 WEST LAKE ROAD
TN. OF SKANEATELES, NY

archite ct

PROJ: 24082

DATE: 27 MAR 2025

3 OF 3